

1. Borings #1 - #4 shall be a minimum of 30ft.
2. If ledge is encountered within proximity of the basement elevation, ledge probes shall be preformed as required to confirm the profile and elevation of ledge throughout the basement space.
3. If soils are found to be uniform in borings #1 - #3, boring #4 may be eliminated from the scope.
4. Test pit #1 shall be dug such that existing foundation depth can be verified. Care shall be taken to not undermine the existing foundation.



GOFFSTOWN PUBLIC LIBRARY
 Addition and Renovation
 December 11, 2020

